

PRASAR BHARATI  
INDIA'S PUBLIC SERVICE BROADCASTER  
ALL INDIA RADIO: KARGIL (J&K)-194103

Fax/tele 01985-232717/234056&Email: Kargil@air.org.in

All India Radio: Kargil

No: KGL-7(4)/1kW/2016-17-E

/ 621 to 630

Dated: 14.09.2016

M/s \_\_\_\_\_  
\_\_\_\_\_

Subject: Reconstruction of damaged retaining stone masonry wall at All India Radio, Kargil.

Sir,

Quotations are invited for the miscellaneous works as per details below; please quote the rates in the enclosed quotation form for the mentioned work. Your quotation should fulfill the following conditions:-

(A) The quotation should be sent in a **SEALED ENVELOP** sealing with the wax by registered post/Ordinary/ By hand addressed to the undersigned so as to reach the same on or before 03/10/2016 (2 pm). The cover should be super scribed with the following details.

- Heading for which quotation is enclosed.
- Reference to letter of enquiry.
- Due dated of opening of quotation.
- **EMD Rs 2000/- in a separate envelope** (The earnest money deposit (EMD) should be submitted along with tender in the form of DD/ Pay order /FDR payable at Kargil in favour of DDO, All India Radio, Kargil.

(B) Other terms and conditions of accepting quotation:-

1. Firm should enclosed copy of the valid License / TAN No. etc issued from Govt. authority along with other relevant documents.
2. Forwarding and freight charges up to destination if applicable and charges as required in the Quotation form.
3. A photo copy of VAT indicating Tin No and list of trading items may please be enclosed Deduction of VAT at appropriate rates under J&K value added tax clearance certificate in the prescribed form issued by assessing authority concerned should to be attached with the quotation of rates.
4. Excise duty: - The firm should furnish the details of Excise Duty charges to be paid by them, separately in clear terms, wherever it is applicable.
5. **TERMS OF PAYMENT:-**
  - (i) No advance payment will be made.

	in the item no-1. 6. All the material shall be got approved/inspected by the representative of this office before start the work, the quantity shown is tentative; payment shall be made on the basis of actual measurements.			
--	--	--	--	--

**Terms and conditions:**

1. Validity of quotation 3 months.
2. The delivery period/ completion period- One month
3. WCT/service tax or any other applicable tax etc will be deducted at source at applicable rate.
4. Payment (100%) will be made after completion of work satisfactorily within one month.
5. Rates should be quoted per unit. Payment shall be made on actual measurement at site.
6. Terms of Delivery: - At All India Radio, Kargil. Baroo, Kargil.  
Inspection: - Material is subject to pre-dispatch inspection.
7. Consignee: Dy. Director. General. All India Radio, Kargil, Baroo, Kargil

*o/c*   
Assistant Engineer

for Dy. Director. General

Name (in capital) \_\_\_\_\_  
Seal: Signature of the Tenderer.  
Date

## Quotation Form

No: KGL-7(4)/1kW/2016-17-E

Dated: 14.09.2016

Subject: Reconstruction of damaged retaining stone masonry wall at All India Radio, Kargil

Last date of receipt of the quotation in this office:.....03/10/2016.....Upto 2 PM


S. No	Description of items	Qty	Unit	Rate	Amount
1.	<p>Reconstruction of retaining stone wall with providing all building construction material such as stone, cement, sand etc at All India Radio, Radio colony, Kargil site as per details and scope of work mentioned below;</p> <p>(a) The size &amp; quantity of damaged retaining wall at site: Stone masonry retaining wall shall be reconstructed at 5 locations/places each of various sizes such as</p> <p>(i) 9Mtrs X 2.4 Mtrs X 0.4 Mtrs (Length X Height X Width) in between the existing stone masonry pillars behind staff quarters block 'C'.</p> <p>(ii) 5Mtrs X 2.4 Mtrs X 0.4 Mtrs (Length X Height X Width) in between the existing stone masonry pillars behind staff quarters block 'D'.</p> <p>(iii) 5 Mtrs X 2.0 Mtrs X 0.4 Mtrs (Length X Height X Width) in between the existing stone masonry pillars behind staff quarters block 'E'.</p> <p>(iv) 3 Mtrs X 2.0 Mtrs X 0.4 Mtrs (Length X Height X Width) in between the existing stone masonry pillars opposite hostel block near fencing.</p> <p>(b) The above retaining stone wall shall be reconstructed with (1cement: 3 sand: 6 aggregate size stone). Its foundation shall be minimum 1' deep as per existing retaining wall of the premises of All India Radio, Radio colony, Kargil.</p> <p>(c) Stone retaining wall shall be reconstructed with stones by properly alignment with existing retaining wall filling of gap among stones with mortar on one side of the wall with proper cementing on edges of stones. The final finish of the above wall with cement plaster teaping with mortar (cement 1; sand 4) including preparing patches in proper shape, raking out joints complete in all respect and as per standard practices.</p> <p>(d) Water curing shall be carried out for the new construction at various stages for 10 days as per standard practices.</p> <p>(e) Including disposal of rubbish to the dumping ground within 50 meter lead as per direction at site so as to clean the area premises.</p>	20 cubic mtrs	Per Cubic Mtr		

2.	Providing and laying cement concrete in coping at the boundary wall ,50mm average thickness (60mm at centre & centre 40 mm at corners) and 400mm width including the cost of centering, shuttering, finishing including demolishing existing coping where ever required, up to height 8'. (ii) 1:1.5:3(1 cement: 1.5 coarse sand:3 graded stone aggregate 20mm nominal size)	25 Mtrs	Per runni ng mtr		
----	---	------------	---------------------------	--	--

- Note: 1. Contractors are advised to visit the site to assess the work before quote their prices.  
2. All the T&P such as ladders/shuttering etc and shall be arranged by the contractor.  
3. As per standard practices for new works water curing shall be carried out for 10 days.

**Terms and conditions:**

1. Validity of quotation 3 months.
2. The delivery period/ completion period- One month
3. WCT/service tax etc will be deducted at source at applicable rate.
4. Payment will be made after completion of work satisfactorily within one month.
5. Rates should be quoted per unit. Payment shall be made on actual measurement at site. Quantity of the work mentioned are estimated and may increase or decrease depending upon the site.

  
Assistant Engineer  
For "Dy. Director. General"